

ADDENDUM NO. 1

May 3, 2018

GLEN CANYON AND GREEN HILLS ROAD BIKE LANE PROJECT

Scotts Valley, Santa Cruz County, California

BID SHEET:

Bid Item 2A of Proposal page P-6 has been changed to read: "Grindings and FDR for shoulder widening in lieu of Base Rock" at a quantity of 2,502 SF.

See attached sheets for new Proposal pages P-5 and P-6

QUESTIONS AND ANSWERS:

Question #1:

I see there are 2 different call outs for shoulder widening, at station 29+75 the shading changes. [For Add Alt 2] Will one still be base rock and the other FDR?

Answer #1:

At sta 29+75 the widening amount becomes too wide for FDR to be feasible, and that widened area should be construction of new pavement only.

Question #2:

The FDR machine is a lot wider than the shoulder widening.

Answer #2:

The small slivers of shoulder widening are all adjacent to roadway FDR, and the machine should be grinding the road and widened area together. If the machine width is too wide, the excess treatment should be of the road not the shoulder.

Question #3:

Is the City interested in utilizing the grindings from this project?

Answer #3:

No. The Sportmen's Club has expressed interest and will be put in touch with the successful bidder.

Bidders shall acknowledge the receipt of this Addendum No. 1 on the Bid Summary page of their proposal. Failure to acknowledge the receipt of this Addendum No. 1 may be cause for rejection of the bid.

CITY OF SCOTTS VALLEY

CONTRACTOR'S BID AND BID PRICE SCHEDULE

GLEN CANYON AND GREEN HILLS ROAD BIKE LANE PROJECT

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item	Description	Quantity	Unit	Unit Cost	Total Cost
1	MOBILIZATION	1	LS		
2	CLEARING AND GRUBBING	1	LS		
3	MILLING	122,854	SF		
4	ASPHALT CONCRETE TYPE B	3,332	TON		
5	CLASS 2 AGGREGATE BASE ROCK	858	TON		
6	EARTHWORK	521	CY		
7	CONCRETE CURB	90	LF		
8	PAVEMENT MARKINGS	1	LS		
9	ROADSIDE SIGNS	6	EA		
10	EROSION CONTROL	1	LS		

PROJECT BASE BID TOTAL (IN NUMBERS)

PROJECT BASE BID TOTAL (IN WORD)

Add Alt	Description	Quantity	Unit	Unit Cost	Total Cost
1	CONSTRUCT SLURRY SEAL	169	TON		
2	FULL DEPTH RECLAMATION	63,665	SF		
2A	GRINDINGS AND FDR FOR SHOULDER WIDENING IN LIEU OF BASE ROCK	2,502	SF		
2B	CEMENT FOR FDR (@5%)	63,665	SF		
4	CONCRETE RESURFACING, AND REMOVABLE BOLLARDS	1	LS		
5	PAVEMENT MARKINGS	1	LS		

TOTAL BASE BID PLUS ADDITIVE BID ITEMS (IN NUMBERS)

TOTAL BASE BID PLUS ADDITIVE BID ITEMS (IN WORD)

Signature

Printed Name

Title

(IMPORTANT NOTICE: If bidder is a corporation, the legal name of the corporation shall be set forth above, together with the signature of the officer or officers authorized to sign contracts on behalf of the corporation; if bidder is a co-partnership, the name of the firm shall be set forth above, together with the signatures of the partner or partners authorized to sign contracts on behalf of the co-partnership; and if bidder is an individual, said bidder's signature shall be placed above.